TANKPUT 19 VOPAK TERMINAL

TANK PROTECTION PROJECT

Project Name Main Contractor Location Product Total Tonnage Delivery Date Tankput 19 VOPAK Terminal Geka Bouw B.V. Rotterdam, Netherlands Sheet Piles & Capping Beams 425 MT 2009

INTRODUCTION

ESC after working very closely with Europile BV in the Netherlands for several years experienced a major breakthrough into Europe with this order.

VOPAK Terminal in Rotterdam, Netherlands needed to have an impervious fire proof barrier put in place under the Netherlands Government legislation. The oil tanks had to have a perimeter that would withstand the possible scenario of a massive failure of the tanks and all the contents flowing out into the surrounding area. In addition, this liquid could well be on fire at the time so the perimeter had to cater for this potential issue as well. Several alternatives were lobbied by various contractors.


Geka Bouw B.V. won the project with a sheet pile option supplied by ESC. ESC worked closely with Geka Bouw B.V. through its agent in Europe, Europile B.V..

e, Europile B.V..

ESC SCOPE OF SUPPLY

SHEET PILES & CAPPING BEAMS

Calculations were carried out by ESC in order to ensure that the stringent requirements of the Client (Royal Vopak N.V.) and the Contractor were met whilst at the same time the budget constraints needed to be adhered to. All sheet piles were painted on the top 4 metres (both sides) with 375 microns of Jotamastic 87 black paint. The capping beams were completely coated using the same paint and thickness. All painting works were carried out in the ESC factory in China.



Extra clutches were sent along with the shipment to ensure that if any special corners were needed to be turned or obstacles caused a variation in the driving line then Geka Bouw BV was able to perform the onsite fabrication without any delays to the project timetable. The Bill of Quantities were as follows:

- ESC-EU12 Steel Sheet Piles in lengths 8-9m (404 tons)
- Capping Beam in 11.8m length (21 tons)



Tankput 19 VOPAK Terminal Project

CARGA DE BUQUES





INSTALACION EN EL SITIO







