

O			
N			
M			
L			
K			
J			
I			
H			
G			
F			
E			
D			
C			
B			
A			
Issue	Revision	Date	Initial

Notes:

ESC Client:

Project Title:




Drawing Title:
SP-25H Steel Sheet Piling

Stamp: _____
Signature: _____

SHOP DRAWING

Designed LLI	Drawn LLI	Checked BILL	Rev.
Scale 1:10 (A4)	Date 20-12-2012	Job No.	



SP-25H Steel Sheet Piling

COMBINED PILE PROPERTIES

SERIES	UNIT WIDTH W [in] (mm)	HEIGHT H [in] (mm)	THICKNESS t [in] (mm)	MASS [lb/ft] (kg/m)	MASS [lb/ft ²] (kg/m ²)	TOTAL MODULUS [in ² /ft] (cm ³ /m)	TOTAL MOMENT OF INERTIA [in ⁴ /ft] (cm ⁴ /m)	Coating Area both sides [ft ² /ft] (m ² /m)
SP-25H	35.43 (900)	11.81 (300)	0.520 (13.2)	75.94 (113)	25.79 (126)	29.95 (1610)	178.68 (24400)	3.05 (3.05)